

## NOTES:

- 1. TRENCH SHALL BE BACKFILLED AND COMPACTED IN ACCORDANCE WITH WSDOT 7-08.3(3).
- 2. BEDDING MATERIAL SHALL BE PEA GRAVEL OR APPROVED EQUAL. PIPE ZONE BACKFILL SHALL BE PEA GRAVEL (OR APPROVED EQUAL) TO THE SPRING LINE FOR RIGID PIPE AND TO A DEPTH OF 6" ABOVE THE CROWN FOR FLEXIBLE PIPE AS SHOWN ABOVE.
- 3. FOR EXISTING ROADS, BACKFILL MATERIAL ABOVE THE PIPE ZONE SHALL BE 1½" CRUSHED ROCK. FOR NEW ROAD CONSTRUCTION, BACKFILL MATERIAL ABOVE THE PIPE ZONE SHALL BE GRAVEL BORROW OR SELECT BORROW IN ACCORDANCE WITH WSDOT 9-03.14 OR 1½" CRUSHED ROCK OR AS APPROVED IN WRITING BY THE CITY ENGINEER.

1	Added Note 3.	8/3/11		
Rev No.	Revisions	Date		
Approved: June 17, 2005			City of *BONNEY ***********************************	Dwg No: SD1
City Engineer Date				TYPICAL STORM DRAIN
STORM DRAIN STANDARD DETAIL				PIPE TRENCH SECTION